

Revised on 8/5/2024

Tennessee Schools for the Deaf Promethean ActivPanel 9 Specifications

Tennessee Schools for the Deaf
2725 Island Home Blvd.,
Knoxville, TN 37920

Contact Person:
Michelle Swaney, Operations Director
m.swaney@tsdeaf.org
(865) 696-0116

Statement of Procurement Need

Tennessee Schools for the Deaf, Knoxville campus, ("TSD") needs to replace outdated Promethean ActivPanels for classroom instruction and meetings/conference spaces in the Upper School (building – Alan J. Mealka High School, #440) and provide training for staff on the new Promethean ActivPanel. Promethean ActivPanels are interactive boards which also have the necessary features and components to integrate with the districts visual emergency messaging system for Deaf and Hard of Hearing students and staff. Updating panels will further enhance the emergency visual messaging system allowing for the incorporation of American Sign Language videos to deliver signed messages for students and staff. Promethean ActivPanels are the only interactive/smart panels with Panel Management for the IT department to centrally manage all panels and ActivInspire which allows for the development of interactive lessons using multimedia rich content. TSD teachers have utilized ActivInspire for over six (6) years and have hundreds of ActivInspire lessons that are incompatible with any other active board. Promethean carts will be purchased for a portion of the boards for mobility purposes. All purchased boards will need to be installed at TSD campuses in accordance with the following specifications.

In addition, TSD needs to replace current stationary wall mounts for the V9 75" Promethean boards in the elementary schools on the Knoxville and Nashville campuses with Promethean AP-ASW-70 adjustable height mounts.

Project Scope

1. Project quote/bid should include estimated lead times for Promethean Panels. Confirmed lead times for shipment to be provided within 5 business days of receipt of approved PO.

Installation, and removal to be completed within 30 days of confirmed shipment date. **Project required to be completed and invoiced no later than October 31, 2024.**

2. Provide, install Promethean ActivPanel 9 boards at the Knoxville campus, building #440 onto selected wall surfaces and de-install as specified and appropriate (see Attachment A Promethean Panel & Cart Quantities for campus/building location and quantity).
3. De-install current V9 75" boards on stationary wall mounts in the elementary schools at the Knoxville and Nashville campuses, remove stationary wall-mount, provide Promethean AP-ASW-70 adjustable height mounts and re-install V9 75" boards with Promethean AP-ASW-70 mount (with adjustable wall mount) as specified and appropriate (see Attachment A Promethean Panel & AP-ASW-70 mount Quantities for campus/building location and quantity).
4. Staging on-site for installation to include the following:
 - a. Unpack new systems from shipping boxes and inspect components for any damage.
 - b. Notify Reseller Project Manager of any discrepancy or damage regarding the shipment of Reseller equipment.
 - c. Shall be responsible for coordinating the replacement and installation of any identified equipment that is materially damaged during the course of its performance under this agreement.
 - d. Organize system components, peripherals, and hardware for deployment.
5. Installation, De-installation, and Transport of boards to include:
 - a. Confirm placement of component per TSD instructions and install wall mount or install board on wall spaces as specified by the customer.
 - b. Shall install and/or de-install and re-install ActivPanels on wall spaces as identified by TSD. Installation shall be performed in a professional manner, and that all equipment is installed in accordance with all applicable laws, codes, and regulations.
 - c. Configure and confirm connection to the appropriate campus network.
 - d. Ensure TSD sign-off and acceptance of all equipment;
 - e. Remove shipping materials and boxes from each location and dispose of materials off-site in a location to be determined by vendor;
 - f. All cables for the Promethean ActivPanel 9 boards should be neatly dressed. This includes coiling any slack in the cables and securing the slack behind the board;
 - g. Replace current stationary wall mounts for the V9 75" Promethean boards in the elementary schools on the Knoxville and Nashville campuses with Promethean AP-ASW-70 adjustable height mounts
6. Promethean ActivCare Standard Warranty shall be included (3-year warranty). The Promethean ActivCare Plus (Warranty Enhancement) shall be quoted (five-year (5-year) warranty in addition for the agency to review and select if funds are available.
7. Provide Promethean V9 ActivPanel Essentials one-day on-site training session for teachers and staff on the Knoxville campus.
8. All bidders shall be required to be an authorized dealer or licensee for the Promethean ActivPanels.
9. Required Contractor's License: The Contractor shall have and actively maintain the below contractor's license during the entirety of the installation/project and throughout any beforementioned warranty period.

a. S-Audio Visual Systems and S-Low Voltage Cabling

Attachment A - Promethean Panel & Cart Quantities

Campus location:

TSD Knoxville - (2725 Island Home Blvd, Knoxville, TN 37920)

<u>Item & Description</u>	<u>Mounting</u>	<u>Quantity</u>	<u>Installation</u>	<u>Building</u>
ActivPanel 9 75" boards – 2x Pen, Vesa Mount, WiFi Module & cable pack included	Wall	32	Yes - 32	Alan J. Mealka High School building (various rooms)
ActivPanel 9 75" boards – 2x Pen, Vesa Mount, WiFi Module & cable pack included	Wall	2	Yes – 2	Edmunds & Annex (various rooms)
De-install V9 ActivPanels on stationary wall mounts, re-install with Promethean AP-ASW-70 mount (adjustable wall mount)	Adjustable Wall Mount	21	Yes - 21	Elementary building 419 (various rooms)
V9 Promethean ActivPanel Essentials On-site Training	N/A	1	N/A	Location TBD

TSD Nashville (on the Tennessee School for the Blind campus)

(115 Stewarts Ferry Pike, Nashville, TN 37214)

<u>Item & Description</u>	<u>Mounting</u>	<u>Quantity</u>	<u>Installation</u>	<u>Building</u>
De-install V9 ActivPanels on stationary wall mounts, re-install with Promethean AP-ASW-70 mount (adjustable wall mounts in Building 13, Cottages 7 & 8)	Adjustable Wall-mount	13	Yes - 13	Tennessee School for the Blind Campus
V9 75" boards – 2x Pen, Promethean AP-ASW-70, WiFi Module & cable pack included -	Adjustable Wall-mount (Promethean AP-ASW-70)	5	Yes – 5	Tennessee School for the Blind Campus

(adjustable wall mount - Cottage 7)				
--	--	--	--	--